OFFICE OF THE ASSISTANT DIRECTOR OF AGRICULTURE, MANDYA CIRCLE.

Abstract Notification.

The attention of the public is invited to this office notification, dated 9th, December 1939 calling for tenders for supply of articles to the Irwin Canal Farm, Mandya, published on pages 2600-2602, Part VI of the *Mysore Gazette*, dated 21st December 1939.

The date and hour for receiving tenders is 3 P.M. of 15th January 1940.

K. KRISHNAMURTI,
Assistant Director.

OFFICE OF THE JUNIOR ASSISTANT BOTANIST, GOVERNMENT EXPERIMENTAL FARM, HIRIYUR.

Abstract Notification dated 25th December 1939.

The attention of the public is invited to the detailed notification dated 25th December 1939 calling for tenders for the purchase of jaggery manufactured on the Government Experimental Farm, Hiriyur, published on pages 11-12, Part VI of the *Mysore Gazette*, dated 4th January 1940.

The date fixed for the receipt of tenders is 22nd January 1940.

C. PUTTIAH,
Agricultural Inspector in-charge,
Junior Assistant Botanist
in-charge, Babbur Farm.

GOVERNMENT OF MYSORE—ELECTRICAL DEPARTMENT.

OFFICE OF THE CHIEF ELECTRICAL ENGINEER IN MYSORE, BANGALORE.

Notification dated 5th January 1940.

CARTING TENDER FOR THE ELECTRIFICATION OF SAKLESPUR TOWN.

Sealed tenders superscribed as "Tender for carting materials for the Electrification of Saklespur Town" will be received in the Office of the Chief Electrical Engineer up to 2 P.M. on Friday the 26th January 1940, for conveying materials required for the Electrification of Saklespur Town.

The materials will have to be carted from any or all of the following places to different work-spots along the abovementioned town or from the following places :—

(*a*) Electrical Department Stores or Railway Station at Hassan.
(*b*) Electrical Department Stores at Belur.
(*c*) Electrical Department Stores at Chikmagalur.

Each tender shall be accompanied with a deposit of Rs. 100, without which the tenders cannot be considered.

The rates to be tendered shall be in the following form and should be entered in words as well as in figures :—

No.	Details	Unit	Rate per mile	
			By Road	By cross country
			Rs. a. p.	Rs. a. p.
1	Wooden poles 26′ long	Cart of 4 poles		
2	Do 35′ ,,	Per pole		
3	Do 40′ ,,	,,		
4	Do 45′ ,,	,,		
5	Tabular steel poles 30′ long	,,		
6	Do 40′ ,,	,,		
7	Do 45′ ,,	,,		
8	Fabricated steel poles 46′-6″	,,		
9	Angle iron and other steel structural materials, including rails and rolled steel I-beams of sizes up to and including a length of 30 ft.	1,500 lbs.		
10	Suspension insulators in crates of 6 units each	18 crates		
11	All other materials such as conductors, ground wire, guy wire, bolts and nuts, clamps, distribution insulators, turn-buckles, cement and other miscellaneous materials	1,500 lbs.		

The Chief Electrical Engineer is at liberty to accept one or more tenders as he deems fit and reserve the right to reject any or all the tenders without assigning any reasons therefor. He is also at liberty to order the transport of materials by the Departmental lorries, hand-carts or by head-loads and the contractor cannot claim any compensation on that account.

On receipt of communication of the acceptance of tender, the tenderer will be required to deposit a further sum of Rs. 100 as earnest money repayable after satisfactory and complete execution of the contract and to sign an agreement with the Department to guarantee satisfactory execution of the contract.

When once a tender is accepted, the accepted rates cannot be enhanced on any account. The contractor may use either country carts or lorries for the conveyance of the materials, but he will be paid only on the unit basis referred to above. No departmental help will be given for loading or unloading the materials.

The successful tenderer shall be prepared to commence the execution of the contract as soon as an agreement has been entered into by him. The conveyance of the materials should be do ne in an expeditious manner as and when required by the Superintendent of Transmission Lines or his authorized representatives, so as not to inconvenience or delay in any manner the construction of the above lines.

The accepted tenderer shall arrange to have one of his representatives in each of the places mentioned above to take instructions regarding the items of materials to be carted and shall arrange to convey the materials as and when required within not more than 24 hours of notice in that behalf. In case of failure to do so, the Department reserves the right to make its own arrangements for conveying the materials and any extra cost incurred by the Department on that account will be recovered from the contractor.

The contract will be liable to be terminated at the discretion of the Chief Electrical Engineer, if the conditions of the contract are not fully complied with and the earnest money deposited will be forfeited to Government.

In all cases of dispute, the decision of the Chief Electrical Engineer will be final.

M. HAYATH,
For *Chief Electrical Engineer.*

OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, MYSORE.

Notification dated 5th January 1940.

1. Sealed tenders in triplicate will be received at the office of the Superintendent, Power and Lighting, Mysore, superscribed with the name of the work noted below.

2. A sum of rupees three hundred and sixty (Rs. 360) is required to be sent along with the tender in cash or currency or cheque drawn in favour of the Superintendent, Power and Lighting, Mysore or order, being the earnest deposit. Tenders not accompanied with the said deposit will not be accepted.

3. The plans connected with the work may be seen at the office of the undersigned at all working hours. The same will be made available on payment of Rs. 3 per set, if required.

4. The tenders should be drawn up strictly in conformity to the specifications furnished, writing out the rate at which, each item of work will be executed in figures as well as in words failing which no cognizance will be taken of the tender. No items other than those noted in the statement should be included, as the items cover provision for all sundries that are necessary for the execution of the work to meet with the requirements of the Department, including painting and colour washing to suit the finish of the walls, etc.

5. Materials to be used on the work should be of best quality conforming to the specifications of this Department and B.S. or A.I.E.E. specifications. Mention should also be made of the manufacture and the catalogue numbers of the materials offered. Teakwood planks to be used on the work should be free from knots, cracks and should be well seasoned. No planks less than 12″ in width will be permitted to be used unless it is to make up the difference in size of the board required. Only lap joints should be adopted in all cases.

6. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

7. The successful tenderer will be required to execute an agreement within two days from the date of communication of acceptance of the tender. He should send samples of all the materials required for the work mounted on a board and start the work after obtaining the approval of the undersigned with regard to the same within a week, from the date of communication of acceptance. Failure to adhere to the conditions above will entail forfeiture of the earnest deposit and adoption of such measures as are necessary for expediting the work otherwise entirely at his risk. He should also bind himself to execute the work strictly adhering to the wiring rules of this Department as well as those of I.E.E. He should also be prepared to adopt changes in the location of lighting fixtures, control points, etc., that might be desired by the undersigned during the progress of the work without any obligation if the tender is not materially affected thereby. The wiring adopted being in

lead covered cable sharp corners should invariably be avoided. The control switches, wall plugs, etc., should be grouped and located at inconspicuous corners. The wall plug points should be placed at heights not more than a foot from floor level. The height of switch points should vary between 3 and 4 feet above floor level.

8. The undersigned reserves the right to reject the work either in full or in part if the same is not executed according to the above specifications or is not satisfactory as regards workmanship.

9. Special care should be taken to afford metallic continuity and to provide efficient earthing to the installation as the system of wiring adopted is in lead covered cables.

10. *Name of the work.*—Installing Electric Lights and Heating Circuit, etc., to the District Hospital at Mandya (Ground Floor).

11. *Last date and time of receiving the tender.*—At 3 P.M. on the 22nd January 1940.

12. *Last date and time for opening the tender in public.*—At 4 P.M. 22nd January 1940.

13. A period of twelve weeks from the date of acceptance of tender will be allowed for the completion of the work in all respects. If the installation is not handed over to the Department with service on the due date, the Department will arrange to take charge of the installation at whatever stage it might be and arrange for completion of the work through any other agency, at the risk of the tenderer.

14. The firm executing the work should arrange while handing over the installation to this Department to pass a certificate of guarantee for the continuance of satisfactory service to the installation for a period of 12 calendar months from the date of handing over charge to this Department, while uninterrupted power supply is maintained. Further, it will be obligatory on the part of the firm to attend to any defects in the installation that might crop up during the above period without any return for service rendered.

15. *Details of work.*—The quantities given in the annexed statement are not guaranteed and are subject to variation at the time of executing the work.

Installing electric lights and heating circuit, etc., to the District Hospital at Mandya (Ground Floor).

Sl. No.	Names of materials, etc.	Unit	Quantity
	Part I—Mains, sub-mains including control boards.		
1	Supplying and running 3 phase mains in 2″ wrought iron pipe, using No. 19/.083 SWG. 660 volts grade insulated wires, bends and other necessary accessories.	Ft.	25
2	Supplying, fixing and wiring T.W. Board 6′×4′×1″ with battens 4″×2″ equipping it with—		
	(*a*) Two T.P.S.T. 60 amps. 500 volts ironclad switch with fuses for heating sub-mains		
	(*b*) Two T.P.S.T. 30 amps. 500 volts, ironclad switches for lighting sub-mains.		
	(*c*) Three D.P.S.T. 30 amps. 250 volts, ironclad switches for the heating distribution.		
	(*d*) One triple pole, 2-way, 15 amps. par way H.O. Pattern distribution box in metal case, with three 10-15 amps. S.P. circuit switches with reinforced bakelite cover, using No. 19/.083, 19/.052, 7/.044, 7/.036 and 7/.029 SWG. insulated wires and accessories rigidly fixed on 2½″×¼″ angle iron frame and ½″ rear board	No.	1
3	Do sub-board 4′×4′×1″ with 4″×2″ battens and ½″ rear board, well supported with the wall, using expansion bolts, equipping the same with—		
	(*a*) Three 60 amps. 500 volts ironclad service cut-outs for heating.		
	(*b*) Three 30 amps. 500 volts ironclad service cut-outs for lighting.		
	(*c*) Three D.P.S.T. 30 amps. ironclad switches with fuses for hearting distribution.		
	(*d*) One triple pole 2-way ,15 amps. per way distribution box in metal case with 3 of 10 to 15 amps. S.P. circuit switches, using No. 19/.052, 7/.044, 7/.036, 7/.029 SWG. insulated wires and accessories	No.	1
4	Supplying and laying No. 19/.064 SWG. 3 core V.C. insulated, lead-covered, double steel tape armoured under ground cable suitable for 1,000 volts working pressure in a trench of 3 ft. deep and surrounding the same with 3″ of fine sand, enclosing the ends in indoor type cast iron junction boxes of approved design filled with insulating compound, using 2″ G.I. pipe across the verandah for enclosing the cable (heating) and using accessories	Ft.	275

Sl. No.	Names of materials, etc.	Unit	Qantity
	Supplying, fixing and wiring bulk head fittings with cast iron enamelled reflector, etc., as above	..	3
5	Do Do $6''\times\frac{1}{2}''$ O.C. brackets complete with O.C. B.C. lamp holder, $10''\times5''$ white opal shade, as per specification above	..	20
6	Do do for china counter weights, complete with porcelain 2-plate ceiling rose, ring, pulley and guide, lead shots, flexible cord, etc., equipped with 'benflux' fittings, complete with shade, etc., using necessary accessories, as per specification above.	..	2
7	Supplying and fixing 'MYSORE' lamps 150 watts 230 volts, B.C. gas filled clear	..	1
8	Do do 100 watts clear	..	26
9	Do do 100 watts internally frosted ..	..	2
10	Do do 60 watts do	..	41

Notification dated 5th January 1940.

1. Sealed tenders in triplicate will be received at the Office of the Superintendent, Power and Lighting, Mysore, superscribed with the name of the work noted below.

2. A sum of (Rs. 250) Rupees two hundred and fifty only is required to be sent along with the tender in cash or currency or cheque drawn in favour of the Superintendent, Power and Lighting, Mysore or order, being the earnest deposit. Tenders not accompanied with the said deposit will not be accepted.

3. The plans connected with the work may be seen at the office of the undersigned at all working hours. The same will be made available on payment of Rs. 3 per set, if required.

4. The tender should be drawn up strictly in conformity to the specifications furnished writing out the rates at which each item of work will be executed in figures as well as in words, failing which no cognizance will be taken of the tender. *The type of wiring adopted being in conduit embedded in the wall it has been arranged to cut open the Grooves for laying the conduit, to plaster and finish the surface damaged through the agency of the Public Works Department. The tender should comprise provision exclusively for the electrical portion of the work.* No items other than those incorporated in the statement should be included in the tender as the items cover provision for all the necessities to the satisfactory execution of work.

5. Materials to be used on the work should be of best quality conforming to the specification of this Department and B.S. or A.I.E.E. Specifications. Mention should also be made of the manufacture and the catalogue numbers of the materials offered. Teak wood planks to be used on the work should be free from knots, cracks and should be well seasoned. No plank less than 12″ in width will be permitted to be used unless it is to make up the difference in size of the board required. Only lap joints should be adopted in all cases.

6. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

7. The successful tenderer will be required to execute an agreement within two days from the date of communication of acceptance of the tender. He should send samples of all the materials required for the work mounted on a board and start the work after obtaining the approval of the undersigned with regard to the same within a week, from the date of communication of acceptance. Failure to adhere to the conditions above will entail forfeiture of the earnest deposit and adoption of such measures as are necessary for expediting completion of the work otherwise entirely at his risk. He should also bind himself to execute the work strictly adhering to the wiring rules of this Department as well as those of I.E.E. He should also be prepared to adopt changes in the location of lighting, fixtures, control points, etc., that might be desired by the undersigned during the progress of the work without any obligation if the tender is not materially affected thereby. It may be noted that the control switches of the lighting outlet should be grouped and located at a height between 3′ to 4′ above floor level as per directions at the time of the execution. The wall plug points together with their control should be located one foot above floor level in general.

8. The undersigned reserves the right to reject the work either in full or in part if the same is not executed according to the above specifications or is not satisfactory as regards workmanship.

9. Special care should be taken to afford metallic continuity and to provide efficient earthing to the installation as the system of wiring adopted is in conduit.

10. *Name of the work :*—Installing Electric lights, etc., to the Western Extension of Exhibition Buildings, Mysore.

11. *Last date and time of receiving the tender* :—At 3 P.M. on the 29th January 1940.

12. *Last date and time for opening the tender, in public* :—at 4 P.M. on 29th January 1940.

13. A period of four months from the date of acceptance of tender will be allowed for the completion of work in all respects. If the installation is not handed over to the Department with service on the due date, the Department will arrange to take charge of the installation at whatever stage it might be and arrange for completion of the work through any other agency at the risk of the tenderer.

14. The Firm executing the work should arrange while handing over the installation to this Department to pass a certificate of guarantee for the continuance of satisfactory service to the installation for a period of 12 calendar months from the date of handing over charge to this Department, while uninterrupted power supply is maintained. Further, it will be obligatory on the part of the Firm to attend to any defects in the installation that might crop up during the above period without any return for service rendered.

15. *Details of work* :—The quantities given in the annexed statement are not guaranteed and are subject to variation at the time of executing the work. Further, the execution of work in the first floor may have to be deferred, if the structure is not completed by the time the work is completed in the ground floor. It should be noted that the Department does not bind itself to allow any enhanced rate for the portion of the work executed.

INSTALLATION OF ELECTRIC LIGHTS TO THE WESTERN EXTENSION OF THE EXHIBITION BUILDINGS, MYSORE.

	Part I—Mains and Control Equipment.	*Quantity.*
1.	Supplying, fixing and wiring on the board available a T.P.S.T. 100 amps. knife switch mounted on slate base with renewable cartridges using No. 19/.083 SWG. insulated wire 660 volts grade and accessories ..	1
2.	Do 30 amps as above using No. 7/.044 S.W.G. insulated wire and accessories ..	1
3.	Supplying and laying No. 19/0.083 SWG 3 conductor V.C. insulated lead covered double steel tape armoured jute served underground cable for 1,000 volts pressure in a trench 3' deep surrounding the same with 3" of fine sand enclosing the ends in pole and indoor type C.I. junction boxes of approved design, tapping from the 25 cycle feeder at the distribution board of the pump house in block 'D' (the cable below the flooring of the pump house and near the approach to the verandah of the building being carried in 40' length of G.I. pipe of 2" dia.) using necessary accessories ..	275'
4.	Do No. 7/0.044 SWG 3 conductor cable tapping from 60 cycle feeder at the distribution board of the pump house in block 'D' as per specifications ..	275'
5.	Supplying and running 3 phase mains in 2" W.I. pipe embeded in the wall using No. 19/0.083 SWG insulated wire for 660 volts pressure and accessories. ..	35'
6.	Do do. do in 1" W.I. pipe with No. 7/.044 SWG insulated wire, etc., as above ..	35'
7.	Supplying, fixing and wiring on a T.W. board 4'×4'×1" with battens and rear board equipping it with 6 D.P.S.T. ironclad switches for 30 amps. with fuses, and 3 D.P.S.T. ironclad switches for 15 amps. with fuses enclosing the full equipment in a box made of $\frac{3}{8}$" thick compressed cement asbestos sheet mounted in the niche made in the wall provided with T.W. panelled shutters with pin head glass panes 1" brass 6 lever lock and key, etc., using No. 37/.083, 7/.064 and 7/.036 SWG insulated wires and accessories ..	1
8.	Earthing ..	2
	Part II—Interior Wiring.	
1.	Supplying, fixing and wiring in 1" and $\frac{3}{4}$" heavy guage welded conduit with flush mounting accessories, such as large round junction boxes, through and terminal boxes with fibre cover, bends, etc., embeded in the wall for lighting outlets complete with 5 amps. S.P. flush type control switches with cream bakelite plate, 2 plate bakelite ceiling rose all white, using	

Quantity.

No. 7/.044 and No. 7/0.029 SWG insulated wires for mains and taps, respectively and accessories ($\frac{3}{4}$" conduit is proposed only in the roofing).

Ground Floor 34
First Floor 34

2. Do do for wall plug outlets complete with 5 amps. flush type wall plugs controlled by a 5 amps. S.P. flush type switch with cream bakelite plate, etc., as per specifications above.

Ground Floor 20
First Floor 20

3. Do do in $\frac{3}{4}$" heavy guage welded conduit embeded in the wall for wall plug outlets as above using No. 7/.036 and 7/.029 SWG insulated wires for mains and taps, respectively and accessories.

Ground Floor 12
First Floor 12

4. Earthing conduits, etc. 2

Part III—Lighting Fixtures.

1. Supplying, fixing and wiring B.C.C.G. reinforced bakelite lamp-holders complete with 3 feet of twin flexible No. 40/.0076 green and white opal shades 10"×5" and accessories.

Ground Floor 31
First Floor 34

2. Supplying and fixing $\frac{5}{8}$" braized conduit pendants 2 to 3 feet long complete with stout flanged B.C. lamp-holder 10"×5" tin enamelled shades and accessories.

Ground Floor 3

3. Supplying and fixing lamps 220 volts, B.C. 200 watts white opal gas filled.

Ground Floor 34
First Floor 34

M. M. ALI KHAN,
Superintendent.

OFFICE OF THE ASSISTANT COMMISSIONER, MADHUGIRI SUB-DIVISION, MADHUGIRI.

Tender Notification No. 1 of 1939-40, dated 6th January 1940.

1. Sealed tenders will be received at the office of the Assistant Commissioner, Madhugiri Sub-Division, up to 2 P.M. on 22nd January 1940 for sinking draw wells in the villages of Sira Taluk as noted below.

2. Tenders in the annexed form and addressed to the Assistant Commissioner, in the sealed cover and superscribed as "Tender for well works at (village).....of.....taluk" and the name of the tender should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a treasury receipt of Rs. (noted below) as paid as earnest money to the treasury to the credit of the R. W. S. funds in the name of the Assistant Commissioner, Madhugiri Sub-Division. The earnest money of the successful tenderer will be retained as security for the fulfilment of the contract. Such deposits in cash will not carry any interest.

4. The tenders will be opened in the presence of such of the tenderers as wish to be present in the Taluk Office of Sira on 23rd January 1940 at 1 P.M. by the Sub-Division Officer, Madhugiri. The final acceptance of the tender will rest with the Assistant Commissioner who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. The name of the successful tenderer will be posted on the notice Board in the Taluk Office, Sira and in the Sub-Division Office, Madhugiri, in due course. Within 8 days of the acceptance of the tender the successful tenderer will be required to execute an agreement on a stamped paper of the